



DANE COUNTY DEPARTMENT of PUBLIC WORKS, HIGHWAY and TRANSPORTATION

County Executive
Joseph T. Parisi

1919 Alliant Energy Center Way ♦ Madison, Wisconsin 53713
Phone: (608) 266-4018 ♦ Fax: (608) 267-1533

Commissioner / Director
Gerald J. Mandli

October 15, 2012

ATTENTION ALL REQUEST FOR PROPOSAL (RFP) HOLDERS

RFP NO. 312028 - ADDENDUM NO. 2

WASTE HAULING FROM DANE COUNTY LANDFILL SITE #2

PROPOSALS DUE: Thursday, October 25, 2012, 2:00 PM. DUE DATE AND TIME **ARE** CHANGED BY THIS ADDENDUM.

This Addendum is issued to modify, explain or clarify the original Request for Proposal (RFP) and is hereby made a part of the RFP. Please attach this Addendum to the RFP and **acknowledge it on the bid form.**

PLEASE MAKE THE FOLLOWING CHANGES:

1. **Contract term**

Contract term shall be two (2) years, with three (3) optional one-year extensions.

2. **Waste Volumes**

Dane County typically receives 165,000 – 175,000 tons of waste per year. Waste characterization studies were done at our landfill in 2002 and 2009. These two waste sorts showed that approximately 40-45% of the waste coming to our landfill is construction and demolition debris (C&D).

The volumes we receive fluctuate with the seasons. For example, we typically receive approximately twice as much daily volume during summer days as we do during winter days.

3. **Methods of loading trailers**

The building will have a Marathon Blockpac 3000 compactor and three additional bays for open-top loading of trailers. The goal is to handle the majority of the waste through the compactor. The compactor can handle most C&D materials, with the exception of really large chunks of concrete, etc. Per the manufacturer's specification sheet, the compactor can compact 90 tons/hr. This should be sufficient to keep up with the anticipated volumes in the transfer station.

The compactor will compact waste materials inside the compactor machine into logs up to 10' long. The log is then pushed into the transfer trailer. The log length can be preset to load either 48' or 53' long trailers. The compactor also has a scale system on it to help maximize the weight on the trailers. In addition, Dane County's front-end loader will have a scale system on the loader bucket to track the amount of waste going into each trailer.

The compactor has a center pin for the trailers to attach to the compactor during waste loading.

4. RSBI

Paragraph C.8 – Add “All terms of sample contract shall be negotiable.”