



DANE COUNTY DEPARTMENT of PUBLIC WORKS, HIGHWAY and TRANSPORTATION

County Executive
Kathleen M. Falk

1919 Alliant Energy Center Way ♦ Madison, Wisconsin 53713
Phone: (608) 266-4018 ♦ Fax: (608) 267-1533

Commissioner / Director
Gerald J. Mandli

ADDENDUM NO. 1

FEBRUARY 14, 2008

ATTENTION ALL REQUEST FOR BID (RFB) HOLDERS
RFB NO. 108029 - FURNISH & INSTALL NEW TRUCK SCALE
DANE COUNTY PUBLIC WORKS
MADISON, WI

BIDS DUE: THURSDAY, FEBRUARY 21, 2008, 2:00 PM. DUE DATE AND TIME ARE NOT CHANGED BY THIS ADDENDUM.

This Addendum is issued to modify, explain or clarify the original Request for Bid (RFB), and is hereby made a part of the RFB. **Please acknowledge this addendum on the Bid Form.**

PLEASE MAKE THE FOLLOWING CHANGES:

1. Clarifications

- a. The existing scale is a mechanical scale with levers and one (1) load cell. Remove all existing levers and other scale appurtenances and dispose of at the landfill. There will be no disposal fee charged to the Contractor for disposing of the levers at the landfill.
- b. The Contractor must provide a crane to install the new scale. The County will provide a scale for removal of the existing scale.
- c. Not all of the existing coping on the walls needs to be replaced. Only replace the coping on the end walls, where it is significantly deteriorated. This results in approximately 20 LF of coping replacement. It is solely the Contractor's responsibility to visit the site and verify these measurements.
- d. Perform coping replacement by doweling into the existing concrete and tack-welding the coping to the dowels. Contractor must warranty the coping Work per Construction Documents.
- e. Do not demolish the existing pillars, as this could harm the structural integrity of the pit walls and floor. Work around the existing pillars when installing new pillars. All Work must still meet the loading and warranty requirements described in the Construction Documents.

If any additional information about this Addendum is needed, please call John Welch, Project Engineer, at 608/516-4154.

Enclosures: N/A