



**DANE COUNTY DEPT. OF  
PUBLIC WORKS, HIGHWAY &  
TRANSPORTATION**

1919 Alliant Energy Center Way  
Madison, Wisconsin 53713  
Office: 608/266-4018 ♦ Fax: 608/267-1533  
Public Works Engineering Division

# ADDENDUM 1

April 22, 2021

**ATTENTION ALL REQUEST FOR BIDRFB HOLDERS**

**RFB NO. 321016 - ADDENDUM NO. 1**

**LAKE FARM PARK SHELTER CONCRETE**

---

**BIDS DUE: TUESDAY, APRIL 27, 2:00 PM. DUE DATE AND  
TIME ARE NOT CHANGED BY THIS ADDENDUM.**

---

This Addendum is issued to modify, explain or clarify the original Request for Bid, Proposal (RFB) and is hereby made a part of the RFB. Please attach this Addendum to the RFB.

**PLEASE NOTE THE FOLLOWING CONTRACTOR SUBMITTED QUESTIONS:**

- Q1:** In section 3.10 letter I, it calls for exterior flatwork to use a sheet membrane cure (wet cure). Is this required on this, or will a standard cure and seal work?
- a. If required, it also asks for a application of anti-spall compound. What product is required here? I assume this is not the concrete sealer you call out in 2.01 (Brickform Poly-astic), but want to verify.
- A1:** Sheet membrane cure is not required. Anti-spall compound is not required. A vapor barrier is not required. Standard cure and seal methods should be used.
- Q2:** Plans call for a 12" thick x 24" wide thickened edge, but the description calls for a 5" slab w/ 2'6"x 12" thickened edge. Please clarify what one is correct.
- A2:** The slab is to have a 12" x 24" thickened edge and 5" thickness throughout remainder.

If any additional information about this Addendum is needed, please contact Ryan Shore at 608/445-0109, shore@countyofdane.com.

Sincerely,

*Ryan Shore*

Project Manager

Enclosures:

N/A