



DANE COUNTY DEPARTMENT of PUBLIC WORKS, HIGHWAY and TRANSPORTATION

County Executive
Joseph T. Parisi

1919 Alliant Energy Center Way ♦ Madison, Wisconsin 53713
Phone: (608) 266-4018 ♦ Fax: (608) 267-1533

Commissioner / Director
Gerald J. Mandli

June 29, 2012

ATTENTION ALL REQUEST FOR RFB HOLDERS

RFB NO. 312013 - ADDENDUM NO. 1

WATER SERVICE EXPANSION FOR LF #2

DANE COUNTY LANDFILL SITE #2

7102 U.S. HIGHWAYS 12 & 18

MADISON, WISCONSIN

BIDS DUE: THURSDAY, JULY 12, 2012, 2:00 PM. DUE DATE AND TIME ARE NOT CHANGED BY THIS ADDENDUM.

This Addendum is issued to modify, explain or clarify the original Request for RFB and is hereby made a part of the RFB. Please acknowledge this Addendum on the Bid Form.

PLEASE MAKE THE FOLLOWING CHANGES:

1. Basic Requirements

Under section 1.2, SUMMARY OF THE WORK, add the following:

At time of construction, the north most end of the existing 6" PVC water line will be tied into a 10" PVC line supplying the Waste Transfer Station construction site with water. Contractor shall disconnect the 10" PVC line from the existing 6" PVC line and reconnect it to the proposed 12" Ductile Iron line. Contractor shall cap the existing 6" PVC line at this location after it is disconnected from the 10" PVC line. Cap shall conform to AWWA C900, "Polyvinyl Chloride (PVC) Pressure Pipe and Fabricated Fittings, 4 in. through 12 in. (100 mm through 300 mm) for Water Distribution."

2. City of Madison Specifications

All applicable work and materials shall conform to City of Madison Standard Specifications for Public Works Construction (2012 Edition), Part VII, Water Mains and Service Laterals. This requirement shall supersede any specifications given in the original RFB. This publication is available at the following link:

<http://www.cityofmadison.com/business/pw/documents/StdSpecs/2012/Part7.pdf>

3. Fork Lift

Dane County owns and operates a Lull fork lift on the construction site which will be available to aid with unloading of materials.

4. Asphalt

Contractor is not responsible for replacing asphalt in areas of Owner's parking lots where Contractor removes pavement for excavating trenches.

5. Sanitary Sewer Lateral

There is a sanitary sewer main and a sanitary sewer lateral that the proposed water line will cross but which are not illustrated in the plan included with the original RFB. These lines are near the proposed tie in to the City of Madison water main. Contractor is still responsible for field verifying all utility locations.

6. High Pressure Gas Line Crossing

MG&E shall be notified before Contractor's excavation crosses the high pressure gas line illustrated in the site plan. MG&E will require that MG&E staff be present during all excavations near the high pressure gas lines.

7. Leachate Line

The utility line labeled as "leachate line" in the Site Plan is a sanitary sewer force main carrying landfill leachate.

8. 12" Gas Main

As-built drawings, including elevations and coordinates, of the 12" gas main labeled in the Site Plan which the proposed water line is to pass under will be supplied to the successful bidder for use during construction.